

Integrated Practice and Collaboration

The Cronkite Experience



SUNDT CONSTRUCTION

Terry Abair



HDR ARCHITECTURE

Michael Jackson



Case Study

THE CRONKITE EXPERIENCE

Content:

- The Challenge
- The Pursuit
- Team and Goal Alignment
- Plan the Work & Work the Plan
- Key Design Concepts
- Design to Budget and Process
- Design Time-line and LEAN Processes
- Packaging & Permitting
- Construction & LEAN Processes
- What Success Looks Like

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Case Study

THE CHALLENGE



1. City of Phoenix Build-to-Suit for ASU
2. Downtown Phoenix, AZ
3. 225,000 – 250,000 sf.
4. \$71,000,000 Total Budget
5. 20 months to Program, Design, Permit, Construct and Commission
6. Design / Build + BIM

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

A Public / Public Partnership



The City of Phoenix



Arizona State University



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Project Challenge

PROGRAM CHALLENGE

- 4 months from kickoff to groundbreaking
- 20 months total schedule
- 15 months construction schedule
- Walter Cronkite School of Journalism
- KAET Channel 8
- University Classrooms
- Ground Floor Retail


Added Challenges:

- Public Art
- Utility Company Electrical Substation
- Superflat Studio Floor Requirement
- Vibration Sensitive TV Studio Uses

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Site

DOWNTOWN PHOENIX



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Site

DOWNTOWN PHOENIX



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Pursuit: Our Go – No Go Schedule

Normal Design Time	12 – 15 months
Construction Document Permitting	2 – 4 months
Demo & Utility Relocations	2 – 3 Months
New Construction	15 months
Commissioning	2 months
<u>Owner Occupancy and Soft Start-up</u>	<u>2 months</u>

Total Normal Design, Permit & Construction 35 – 41 months

Our Plan (Commit to 20 months program, design, permit & construct):

7 Permit Packages

9 months to Program, Design and Permit Complete Building


15 months of New Construction Overlapping the Design 4 ½ months

Owner FF&E, Move-in & Soft Start-up 2 ½ months

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Our Go – No Go Design

SCHEDULE CHALLENGE = STRUCTURAL CHALLENGE




Key Concepts:

1. Cast-in-place Concrete
2. Column Hung Form System
3. 8 FT. Maximum Cantilever
4. Maximize Building Footprint
5. 30,000 SF +/- Floor Plates
6. 2 Pours, Maximize PT Pull Lengths
7. Minimize Shear-walls
8. No Basement, No Transfer Girders
9. All Goals Designed to Minimize Deck Cycle Times

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Pursuit

SCHEDULE CHALLENGE = STRUCTURAL CHALLENGE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Pursuit

SCHEDULE CHALLENGE = STRUCTURAL CHALLENGE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

How Did We Get There ?

- Allow Partners to Choose Each Other
- Avoid Shotgun Marriages
- Build the Team
- Alignment of Goals
- Culture of Success where Failure Is Not an Option!
- Work Smart



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Build the Team

CORE DESIGNERS



SUNDT Construction
Construction



HDR Architecture
Architect of Record and MEP

EHRlich ARCHITECTS



EHRlich Architects
Design Architect

CTS
Structural



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Build the Team

KEY SUBCONTRACTORS

Core Subcontractor Partners

- SUNDT - Concrete & Civil
- University Mechanical – HVAC & Plumbing
- Kearney Electric – Electrical & Special Systems
- KT Fab – Glass & Glazing Systems

Additional Qualification & Price Based Selections


- Progressive Contracting Group (PCG) – Framing & Drywall
- Elward – Metal Panel System
- Sun Valley Masonry - Masonry



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Establish Relationships

TEAM INTEGRATION



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Culture of Success

WHAT DOES SUCCESS LOOK LIKE ?

What Does Success Look Like?

- What Defines Success for Each Party?
- Define the Desired End State
- Shared Vision is Shared Success

Critical Concepts:

- Failure is NOT an option
- Speed is critical / make the right decisions early
- Conceive the Whole not the Part
- Consider Consequences to other Systems
- Integration makes Good Design

SUNDT Construction :: HDR Architecture :: Ehrlich Architects


What it's not!

I'm sure glad the hole isn't in our end...



Alignment is Seeking the Same *GOAL*


What it's not!



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Alignment – The Same Bullseye

What it IS!



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Alignment – The Vulcan Mind Meld

What it IS!



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Collaboration – The Efficient Machine

What it IS!



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Collaboration

CO LOCATION & THE VULCAN MIND MELD

What it IS!

- Proximity leads to Communication (it's not always pretty)
- Communication leads to Understanding
- Understanding leads to Respect
- Respect fosters Cooperation



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Integrated Practice

...DON'T GET TOO COMFORTABLE ?



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Cronkite School of Journalism - KAET Channel 8

Design Evolution Log



December 3, 2008

Program S.F.	244,000
Revised S.F.	223,229
Current S.F.	223,229
Delta	20,771

COST MODEL	71,000,000
ACCEPTED CHANGES:	0
CURRENT BUDGET:	71,000,000
TARGET BUDGET:	71,000,000
BUDGET STATUS:	0
REMAINING POTENTIAL:	1,898,431
REJECTED:	0

Excludes "Indirects" -->
Excludes "Indirects" -->

	1/25/2007 DEL	ACCEPTED CHANGES	CURRENT BUDGET	COST PER SQ. FT.	% CHANGE
01 GENERAL REQUIREMENTS	2,019,996	0	2,019,996	\$ 9.05	0.00%
02 SITEWORK	1,532,706	(30,595)	1,502,111	\$ 6.73	-2.00%
03 SUBSTRUCTURE	1,323,592	0	1,323,592	\$ 5.93	0.00%
04 SUPERSTRUCTURE	7,092,010	(157,410)	6,934,600	\$ 31.06	-2.22%
05 EXTERIOR WALL	4,132,040	0	4,132,040	\$ 18.51	0.00%
06 ROOFING	190,687	0	190,687	\$ 0.85	0.00%
07 INTERIOR CONSTRUCTION	5,004,561	0	5,004,561	\$ 22.42	0.00%
08 INTERIOR FINISH	1,813,179	0	1,813,179	\$ 8.12	0.00%
09 SPECIALTIES	47,918	0	47,918	\$ 0.21	0.00%
10 EQUIPMENT & FURNISHINGS	153,171	0	153,171	\$ 0.69	0.00%
11 SPECIAL CONSTRUCTION	7,500	0	7,500	\$ 0.03	0.00%
12 CONVEYING SYSTEM	1,362,023	157,410	1,519,433	\$ 6.81	11.56%
13 FIRE SPRINKLER	595,891	0	595,891	\$ 2.67	0.00%
14 PLUMBING	948,790	0	948,790	\$ 4.25	0.00%
15 MECHANICAL	7,620,653	0	7,620,653	\$ 34.14	0.00%
16 ELECTRICAL	6,259,055	(2,033)	6,257,022	\$ 28.03	-0.03%
Northwind Connection Cost	0	0	0	\$ -	#DIV/0!
LEED Premium	38,396	0	38,396	\$ 0.17	0.00%
Subcontractor Default Insurance	412,422	0	412,422	\$ 1.85	0.00%
Labor Escalation	761,676	0	761,676	\$ 3.41	0.00%
Material Escalation	761,676	0	761,676	\$ 3.41	0.00%
Design Contingency	992,046	32,628	1,024,674	\$ 4.59	3.29%
Subtotal	\$ 43,069,987	\$ -	\$ 43,069,987	\$ 192.94	0.00%
INDIRECTS:					
General Conditions	2,471,690	0	2,471,690	\$ 11.07	0.00%
PL & PD Ins	610,035	0	610,035	\$ 2.73	0.00%
Builders Risk Ins	58,231	(0)	58,231	\$ 0.26	0.00%
G C Bond	415,933	(0)	415,933	\$ 1.86	0.00%
Contractors Contingency	2,772,886	0	2,772,886	\$ 12.42	0.00%
Sales Tax	2,919,849	0	2,919,849	\$ 13.08	0.00%
Contractors O.H. & P.	3,139,117	(0)	3,139,117	\$ 14.06	0.00%
Subtotal	\$ 12,387,741	\$ 0	\$ 12,387,741	\$ 55.49	0.00%
CONSTRUCTION COST	\$ 55,457,728	\$ 0	\$ 55,457,728	\$ 248.43	0.00%
SOFT COSTS					
Design Fees	7,910,994	0	7,910,994	\$ 35.44	0.00%
DESIGN BUILDER CONTRACT	\$ 63,368,722	\$ 0	\$ 63,368,722	\$ 283.87	0.00%
CITY OF PHOENIX SOFT COST					
CoP Soft Cost	7,631,278	0	7,631,278	\$ 34.19	0.00%
Total	\$ 71,000,000	\$ 0	\$ 71,000,000	\$ 318.06	0.00%

Design to Budget Design Evolution Log

COST MODEL - LINE ITEM MANAGEMENT

Key Concepts:

1. Reverse Engineer Owners *Entire Budget*
2. Manage Design to the *Direct Cost Line*
3. *System Accountability by Designer and Trade Contractor*
4. *Cost Breach by D-B Line Item Team Means Asking Entire Project Team for Part of Their Budget or Design Contingency Relief*

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Design Evolution Logs

	Sundt Parametric Cost Model				HDR/SEA Design as of 4/29/08				VARIANCE
	\$/Ut	UT	QTY	Extension	\$/Ut	UT	QTY	Extension	OVER / (UNDER)
EXTERIOR SKIN / ROOFING SYSTEMS									
Concrete Shear Walls									
Concrete shear walls (move from superstructure)	\$51.30	SF	21,545	\$1,105,259	\$0.00	SF	-	\$0	
Level-1, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$57.97	SF	5,000	\$0	
Level-2, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$61.09	SF	3,323	\$202,988	
Level-3, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$61.09	SF	3,323	\$202,988	
Level-4, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$61.09	SF	3,323	\$202,988	
Level-5, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$61.09	SF	3,323	\$202,988	
Level-6, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$59.59	SF	2,890	\$172,216	
Level-7, 18" shear walls, w/ deep form liner, rebar 300 lbs/cy					\$60.82	SF	3,716	\$225,991	
8 Form liner in concrete shear walls	\$7.90	SF	13,296	\$105,038	\$0.00	SF	-	\$0	
11 DEL Item - Sup #03 - Reduce concrete shear walls to min. required.					-\$10,732.00	Ls	1	(\$10,732)	
12 DEL - Sup #07 - Change form liner to 4'x8' reveal w/ light/medium sandblast					-\$24,469.00	LS	1	(\$24,469)	
				\$1,210,296.00				\$1,174,959.52	(\$35,337.38)
Total Square Footage of Metal Panels		SF	34,841			SF	24,898		(9,943)
Exterior Scaffolding					\$275,000.00	LS	1	\$275,000.00	
Exterior Metals				\$0.00				\$0.00	
1 Metal Panels	\$45.00	SF	47,762	\$2,149,290.00	\$45.00	SF	26,522	\$1,193,490.00	
6" 18 ga 16" o.c. w/1 layer Densglass				\$0.00	\$7.26	SF	26,522	\$192,549.72	
R-19 Batt insulation					\$1.00	SF		\$0.00	
2 Copper at Auditorium				\$0.00	\$50.00	SF		\$0.00	
Framing at Auditorium Copper					\$15.37	SF		\$0.00	
3 Metal Column Covers	\$200.00	LF	168	\$33,600.00				\$0.00	

DESIGN & PERMIT SCHEDULE

	Planned	Actual Scheduled
Scope Meeting	10-09-06	10-09-06
Program Verification Blocking & Stacking Complete	12-19-06	11-15-06
Preliminary Design Complete	03-05-07	01-25-07
Site Plan Approval (Key to Project)	04-13-07	01-31-07
Demo / Utility Permit	05-11-07	12-13-07
Foundation Permit	04-10-07	04-11-07
Superstructure Permit	05-22-07	05-27-07
Core & Shell Building permit	08-09-07	06-19-07
Tenant Fit-up Permit	09-07-07	07-19-07

Collaboration


ALL STAKEHOLDERS ARE PART OF THE TEAM



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Remote Collaboration


GOTOMEETING.COM



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Work Smart


BUILDING INFORMATION MODELING



- Visualization in Real Time
- Documents / Quality / Quantity
- Unified Revit Model (Arch, Struct, Mech)
- 4D Scheduling & Sequencing
- 5D Quantity Survey and Cost Analysis
- Analytical Tool

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Workflow



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Rapid Design Evolution

RESPONSIVE DESIGN



Week 2



Week 4



Week 5



Week 7



Week 2

10.25.2006

9 Stories

248,000 sq.ft.

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Rapid Design Evolution

RESPONSIVE DESIGN

Week 4

11.06.2006

7 Stories

242,000 sq.ft.



Week 2



Week 4



Week 5



Week 7



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Rapid Design Evolution

RESPONSIVE DESIGN

Week 5

11.12.2006

6 Stories

217,000 sq.ft.



Week 2



Week 4



Week 5



Week 7



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Rapid Design Evolution

RESPONSIVE DESIGN


Week 6

11 - 14 - 2006

6 Stories + Mech Mezzanine

242,000 sq.ft.

BOD & Preliminary GMP Submittal



Week 2



Week 4



Week 5



Week 6



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

BIM Applied

THREE DIMENSIONAL DATA BASE



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Design Strategy

STRUCTURAL SYSTEM



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Design Strategy

STRUCTURAL SYSTEM



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Design Visualization

BIM (REVIT)



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Design Visualization


BIM (REVIT)



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Clear Communication

DESIGN INTENT



SUNDT Construction, Inc. :: HDR Architecture, Inc. :: Steven Ehrlich Architects

CSJ / EIGHT


OVERALL 3D

MZ-00
9/16/2007 8:31:51 PM

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Clear Communication

DESIGN INTENT



MZ-02

SUNDT Construction, Inc. :: HDR Architecture, Inc. :: Steven Ehrlich Architects

PROJECT NAME
CSJ / EIGHT


ISSUE NAME
MEZZANINE LIGHT FIXTURE POWER

DATE / TIME / USER
9/16/2007 8:32:04 PM

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Clear Communication

DESIGN INTENT



MZ-06

SUNDT Construction, Inc. :: HDR Architecture, Inc. :: Steven Ehrlich Architects

PROJECT NAME
CSJ / EIGHT


SHEET NAME
MEZZANINE STEEL TRANSITIONS

DATE / TIME
9/16/2007 8:32:23 PM

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Clear Communication

DESIGN INTENT



SUNDT Construction, Inc. :: HDR Architecture, Inc. :: Steven Ehrlich Architects	PROJECT NAME CSJ / EIGHT	DATE 9/16/2007 8:32:28 PM	MEZZANINE BALUSTER DETAILS
---	-----------------------------	------------------------------	----------------------------

MZ-07

BIM Coordination Plan


LEAN SHOP DRAWING PROCESS

START DATES	2/19	2/26	3/5	3/12	3/19	3/26	4/2	4/9	4/16	4/23	4/30	5/7	5/14	5/21	5/28	6/4	6/11	6/18	6/25	
DESIGN DELIVERABLES		SUPER STRUCT COMPLETE 3-01-07						SHELL DESIGN COMPLETE 4-09-07				FINAL DESIGN COMPLETE 5-7-07	SUPER STRUCT PERMIT 5-11-07				SHELL & CORE PERMIT 6-14-07			
MEP DELIVERABLES										SAW & DECK BLOCKOUT DWGS		UNDER GROUND COORD DWGS		LEVEL 1 COORD DWGS		LEVEL 2 COORD DWGS		LEVEL 3 COORD DWGS		
BELOW SOG UTILITIES		KICKOFF MEETING #1		KICKOFF MEETING #2		DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	FINAL	ANNOTATE							MROOM	PROC & DEL	
LEVEL 1							DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	FINAL	ANNOTATE		HGR DWGS + L2 SLEEVES, INSERTS	MROOM+ FAB PLAN, SPLS, CL, SFF BOMS	CRSPLS+ PROC & DEL		1ST HALF 2ND FLOOR POUR	2ND HALF 2ND FLOOR POUR	1ST HALF 3RD FLOOR POUR
LEVEL 2								DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	FINAL	ANNOTATE		HGR DWGS + L3 SLEEVES, INSERTS	MROOM+ FAB PLAN, SPLS, CL, SFF BOMS	CRSPLS+ PROC & DEL			TURBIDITY STARTS 6-28
LEVEL 3											DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	FINAL	ANNOTATE		HGR DWGS + L4 SLEEVES, INSERTS	MROOM+ FAB PLAN, SPLS, CL, SFF BOMS	
LEVEL 4													DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	FINAL	ANNOTATE		
LEVEL 5															DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD	DRAW & COORD
LEVEL 6																	DRAW & COORD	DRAW & COORD		
LEVEL 7 & ROOF																				

	5/7	5/14	5/21
DESIGN DELIVERABLES	FINAL DESIGN COMPLETE 5-7-07	SUPER STRUCT PERMIT 5-11-07	
MEP DELIVERABLES	UNDER GROUND COORD DWGS		LEVEL 1 COORD DWGS
BELOW SOG UTILITIES			
LEVEL 1			
LEVEL 2			
LEVEL 3			
LEVEL 4			
LEVEL 5	FINAL	ANNOTATE	HGR DWGS + L2 SLEEVES, INSERTS
LEVEL 6	DRAW & COORD	DRAW & COORD	FINAL

Pre-Construction Clash Detection

NAVIS WORKS




- Collision Detection
- Shop Drawing Coordination

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Pre-Construction Clash Detection

NAVIS WORKS




- Mechanical Room before NavisWorks

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Pre-Construction Clash Detection

NAVIS WORKS




- Mechanical Room after NavisWorks

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Fully Coordinated Construction Model

NAVIS WORKS



- True 3D Deliverables ?

SUNDT Construction :: HDR Architecture :: Ehrlich Architects


The BIM advantage

- **Increased speed of delivery (time saved)**
- **Better coordination (fewer errors)**
- **Decreased costs (money saved)**
- **Greater productivity**
- **Higher-quality work**

Collaborative CA

LEAN SHOP DRAWING PROCESS


- Request for Information
- A Conversation
- Record with a Confirming RFI
- Eliminates the Paper Wars
- Avoid E Mail



SUNDT Construction :: HDR Architecture :: Ehrlich Architects




SUNDT Construction :: HDR Architecture :: Ehrlich Architects




SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects




SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects




SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

FCC Frequency Bands

Architectural Interpretation



- Bla bla bla
- Bla bla bla
- Bla bla bla

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Public Art – Light & Reflection



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

One Year After Contract Award

November, 2007



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

The Results of Successful Collaboration



14.33 months in 120 seconds

SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Construction Schedule

Milestone Description	Original Contract Completion	Actual Schedule Completion		Variance
Notice of Selection	06-Oct-06	06-Oct-06	A	0
Issue Final Program	10-Nov-06	14-Nov-06	A	4
Demo Permit Received	13-Dec-06	13-Dec-06	A	0
Preliminary Design Approved by Executive Committee	22-Jan-07	25-Jan-07	A	3
Official Start of the Contract	05-Dec-06	25-Jan-07	A	50
Site Plan Approved	20-Mar-07	31-Jan-07	A	-49
Mobilize - Begin Demo & Utility Relocations	21-Mar-07	05-Feb-07	A	-46
New Utilities & Site Work Permit Received	20-Mar-07	01-Mar-07	A	-19
Foundation Permit Received	10-Apr-07	12-Apr-07	A	2
Complete Team Mobilization to Site	24-Apr-07	17-Apr-07	A	-7
Start Foundation Construction	11-Apr-07	16-Apr-07	A	5
Superstructure Permit Received	06-Jun-07	29-May-07	A	-7
Shell Building Permit Received	02-Aug-07	10-Jul-07	A	-22
Start Exterior Enclosure	03-Aug-07	01-Aug-07	A	-2
Interior Fit Up Permit Received	30-Aug-07	22-Aug-07	A	-8
Top Out of Structure	30-Oct-07	21-Nov-07	A	21
Power on Date	26-Mar-08	31-Jan-08	A	-55
Penthouse MEP Complete	26-Mar-08	19-Feb-08	A	-37
Start of Building Commissioning	26-Mar-08	01-Feb-08	A	-55
1st Passenger Elevator Operational	24-Apr-08	06-Mar-08	A	-48
Exterior Enclosure Complete	28-Jan-08	23-May-08	A	115
Passenger Elevators Complete	24-Apr-08	22-May-08	A	28
Interior Construction Complete	20-May-08	23-May-08	A	3
Complete Building Commissioning	18-Jun-08	23-May-08	A	-25
Building Substantially Complete (Contract June 11, 2008)	17-Jul-08	30-May-08	A	-47
Start ASU FF&E Installation (Follows Contract Substantial Completion)	01-Jun-08	12-Jun-08	A	11
Complete ASU FF&E Installation	07-Jul-08			
Begin Move in Process (Employee Affects)	15-Jul-08			
1st - Butts in Seats (Occupancy)	17-Jul-08			
Project Final Completion	18-Aug-08			
1st - Classes Held	15-Aug-08			

Lessons Learned

SOFTWARE WORK FLOW

Unified Software Platform

Revit Arch

Revit Struct


Revit Systems (when ready)

Navis for Design Coordination

Unified Project Server (Steelhead / Riverbed Technology)

Fire Protection Designed / Coordinated with Systems

Schedule to allow for Pre-Construction Coordination



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

Lessons Learned

SOFTWARE WORK FLOW

DESIGN MODEL

Architecture: Revit → AutoCAD ADT
Structural: Revit Structure
M/E/P: AutoDesk Building Systems
Fire: None



MANUAL COORDINATION


SHOP COORDINATION MODEL

Architecture: Revit
Structural: Revit Structure
M/P: CAD Duct, Quick Pen
Fire: Quick Pen



NAVIS WORKS COORDINATION

CHALLENGE: Better Integrate Design and Shop Drawing Process



SUNDT Construction :: HDR Architecture :: Ehrlich Architects



SUNDT Construction :: HDR Architecture :: Ehrlich Architects

THE END

SUNDT Construction :: HDR Architecture :: Ehrlich Architects